

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23271-00-00
Spot: NWNENW Sec/Twnshp/Rge: 32-25S-5E
4921 feet from S Section Line, 3668 feet from E Section Line
Lease Name: MOLERA A Well #: 34
County: BUTLER Total Vertical Depth: 2530 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2484		
PROD	5.5	2529		375 SX
SURF	8.625	261		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2016 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/10/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2434', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS CLASS A COMMON 4% GEL 3% CC 100# HULLS & DISPLACED IN CASING. TAGGED CEMENT @ 1720'. LOADED HOLE & PRESSURED CASING @ 250#, HELD OK. RIH W/TBG @ 315', CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL, 2% CC, 1/4# FLOW-SEAL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 P.M., 11-10-2016. CONSOLIDATED OILWELL SERVICES TICKET #51878.

Perfs:

Top	Bot	Thru	Comments
2508	2510	CSG	
2456	2474	CSG	
661	671	CSG	

Remarks: ADMIRE PERFORATIONS WERE SQUEEZED BACK TO SURFACE W/CEMENT / 10 YEAR RULE.

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

166 Form CP-2/3
DEC 21 2016

JK