

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-21274-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 1-28S-5W  
1650 feet from N Section Line, 990 feet from W Section Line  
Lease Name: ZERGER Well #: 1  
County: KINGMAN Total Vertical Depth: 3866 feet

Operator License No.: 32009  
Op Name: SPS, INC.  
Address: 4000 FREIDA  
CHENEY, KS 67025

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 3866       | 2896        | 200 SX   |
| SURF   | 8.625 | 257        |             | 175 SX   |

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2016 12:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: MARK SCHMIDTBERGER Company: \_\_\_\_\_ Phone: (316) 772-0720

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/02/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SET CIBP @ 3510' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2896', PULLED CASING. TRIPPED TUBING INTO 808' SPOTTED 50 SX CEMENT WITH 150 LBS. HULLS & 3% C.C. WAITED 2 HOURS TAGGED AT 726'. TRIPPED TUBING INTO 362' CIRCULATED TO SURFACE WITH 135 SX CEMENT. FELL BACK 88' - TOPPED WITH 20 SX OF CEMENT.

Remarks: COPLAND OUT OF BURRTON BROUGHT CEMENT, ALL CLASS A TICKET #44841.

Plugged through: TBG

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)

Form CP-2/3

*jm*  
DEC 21 2016