

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-199-20436-00-00  
Spot: NENWSWSW Sec/Twnshp/Rge: 7-15S-41W  
1160 feet from S Section Line, 335 feet from W Section Line  
Lease Name: YODER Well #: 1-7  
County: WALLACE Total Vertical Depth: 5200 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY SUITE 2  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13.375	528		410 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2016 12:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: TOMMY Company: MURFIN DRILLING CO., INC. Phone: (620) 453-9121

Proposed Plugging Method: Ordered 310 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

**KCC WICHITA**  
**DEC 14 2016**  
**RECEIVED**

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE  
Date/Time Plugging Completed: 11/15/2016 6:00 PM KCC Agent: EDWIN SCHUMACHER

**Actual Plugging Report:**

**Perfs:**

1st plug @2800 w/50 sx  
2nd plug @1780 w/100 sx  
3rd plug @580 w/90 sx  
4th plug @40 w/25 sx  
  
Rathole 30 sx Mousehole 15 sx

Remarks: BASIC

Plugged through: DP

District: 04

Signed Edw Schumacher  
(TECHNICIAN)

CM

NOV 28 2016

Edw Schumacher  
DEC 21 2016 Form CP-2/3