

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-22473-00-00
Spot: SESWNWNE Sec/Twnshp/Rge: 29-11S-17W
4266 feet from S Section Line, 2274 feet from E Section Line
Lease Name: GLATHART Well #: 8
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3690		250 SX
SURF	8.625	242		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2016 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: CRAIG HUTCHINSON Company: MURFIN DRILLING CO., INC. Phone: (782) 623-0123

Proposed Plugging Method: Ordered 285 sx 60/40 pozmix 4% gel cement, 14 sx gel and 500 # hulls.
FO Tool at 1329' w/325 sx cement.
CIBP at 3585'.
Arb: 3532' - 3545', 3551' - 3556'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2016 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Murfin ran in hole with tubing to 3500'. Quality rigged to tubing and pumped 14 sx gel followed by 50 sx cement w/300 # hulls mixed in. Pulled tubing to 1650'. Rigged to tubing and pumped 150 sx cement w/200 # hulls mixed in to circulate cement up 5 1/2" casing. Pulled tubing. Topped off 5 1/2' casing with 25 sx cement. Hole standing full. Rigged to 8 5/8" surface casing and pumped 10 sx cement to pressure with 200 psi. Shut in pressure 200 psi.

GPS: 39.07130 -099.23080

Perfs:

Top	Bot	Thru	Comments
3551	3556		
3532	3545		

Remarks: QUALITY OILWELL CEMENTING CO. TICKET # 3032

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)


CM

KCC WICHITA

NOV 14 2016

NOV 29 2016

RECEIVED


DEC 21 2016

Form CP-2/3