

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-22305-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 8-29S-9W
1217 feet from N Section Line, 1625 feet from W Section Line
Lease Name: LIBERTY Well #: 1-8
County: KINGMAN Total Vertical Depth: 4650 feet

Operator License No.: 35353
Op Name: OKLAND OIL COMPANY
Address: 110 N. ROBINSON SUITE 400
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4470		
COND	20	65		200 SX
PROD	4.5	4650	2885	225 SX
SURF	8.625	223		175 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/16/2016 12:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN WATSON Company: _____ Phone: (580) 571-7609

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL Witness Type: PARTIAL
Date/Time Plugging Completed: 11/18/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 3940'. SPOT 2 SX CEMENT WITH DUMP BAILER. LAY DOWN 2885' OF 4 1/2" CASING. RUN TUBING TO 1442'. PUMP 65 SX 3% CAC12 CEMENT. PULL TUBING AND WAIT 4 HOURS. TAG PLUG AT 1464'. PULL TUBING TO 950'. PUMP 35 SX CLASS 'A' & 25 SX 60/40 POZ W/4% GEL. PULL TUBING TO 272', CIRCULATED CEMENT TO GEL & 200# HULLS.

Perfs:


Top	Bot	Thru	Comments
4481	4484		
3998	4005		
3992	3995		

Remarks: BASIC ENERGY WAS CEMENTER - TICKET #14689

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)