

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-20075-00-01
Spot: NESE Sec/Twnshp/Rge: 13-29S-8W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: HANDKINS Well #: 1
County: KINGMAN Total Vertical Depth: 4490 feet

Operator License No.: 34848
Op Name: POLLOK ENERGY, LLC
Address: 501 N. 4TH PO BOX 106
PURCELL, OK 73080

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4435	2786	265 SX
SURF	8.625	235		250 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/16/2016 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: DAVID HICKMAN Company: _____ Phone: (620) 253-6588

Proposed Plugging Method: AS PER KCC RULES & REGS.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 11/17/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SET CIBP @ 3940' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2786'. PULLED CASING. TRIPPED TUBING INTO 1230' SPOTTED 35 SX CLASS A CEMENT W/3% CC. WAITED 2 HOURS NO TAG, SPOTTED ANOTHER 35 SX CLASS A CEMENT W/ 3% CC. LEFT OVER NIGHT, TAGGED AT 1256' IN AM. TRIPPED TUBING TO 812' SPOTTED 50 SX CLASS A CEMENT 3% CC. WAITED 2 HOURS NO TAG, SPOTTED ANOTHER 100 SX CLASS A CEMENT W/3% CC. WAITED 2 HOURS TAGGED @ 615'. PULLED TUBING TO 297' AND CIRCUALTED TO SURFACE WITH 160 SX CEMENT.

Remarks: COPLAND OUT OF GREAT BEND, BROUGHT CEMENT.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

DEC 21 2016

Form CP-2/3

1/2