

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-22249-00-00
Spot: E2SWSW Sec/Twnshp/Rge: 27-33S-31W
660 feet from S Section Line, 990 feet from W Section Line
Lease Name: PARITY Well #: 1-27
County: SEWARD Total Vertical Depth: 6293 feet

Operator License No.: 30604
Op Name: RAYDON EXPLORATION, INC.
Address: 1601 NW EXPRESSWAY, STE 1300
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	40		
SURF	8.625	1668		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/19/2016 2:00 AM
Plug Co. License No.: 35226 Plug Co. Name: QUEST DRILLING SERVICES, LLC
Proposal Rcvd. from: CLINT ANDREWS Company: CROWN CONSULTING Phone: (620) 629-3267

Proposed Plugging Method: 1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 80 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 10/19/2016 4:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:


1ST PLUG AT 1715' WITH 50 SX CMT. 2ND PLUG AT 562' WITH 80 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP


District: 01

Signed



(TECHNICIAN)

RECEIVED
NOV 17 2016
KCC DODGE CITY



Form CP-2/3

DEC 21 2016