

15.095.21038-0000

Operator
Martin Oil Producers, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Dalike

Gas Well

S 3 T 29 R 6 E W

WELL LOG

Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 4055'-4080'. 30-45-60-60 Gas to surface in 30 minutes.			Heebner	2895'
10" - 9,200 CFGPD			Lansing	3240'
20" - 25,100 "			Kansas City	3482'
30" - 26,600 "			Stark Shale	3640'
40" - 23,700 "			Mississippi	4052'
50" - 21,900 "			Dolomite	4089'
60" - 23,700 "			Total Depth	4499'
Recovered 150' watery mud. BHP 1286#/45" IF 58#-55# FF 70#-82# FBHP 1355#/60" Temp 124°				
DST #2 - 4082'-4115'. 30-45-120-60				
10" - 4,840 CFGPD				
20" - 6,290 "				
30" - 7,060 "				
40" - 7,060 "				
50" - 14,600 "				
60" - 59,200 "				
70" - 59,200 "				
80" - 78,100 "				
90" - 47,700 "				
100" - 78,100 "				
110" - 59,200 "				
120" - 50,200 "				
IBHP 1413#/30" IF 82#-82# FF 93#/117" FBHP 1415#/60". Recovered 300' mud.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

K.S. Martin
K.S. Martin
President

Signature

Title

5/5/81

Date