

CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED
CORPORATION COMMISSION

OCT 13 1967

10-13-67

CONSERVATION DIVISION
WICHITA, KANSAS

P. Roberts
Administrator
10 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued September 21, 1967.

Operator's Full Name Morris Sitrin, Inc.

Complete Address: P. O. Box 318, Claflin, Kansas 67525

Well Name Waters Well No. # 1

Location C SE SE Sec. 4 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4289'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

The well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:30 AM Day 12/12 Month October Year 1967

The above well was plugged as follows:

57' of 8 5/8" surface pipe, cemented with 235 sacks. 4287' of 4 1/2" long string,
cemented with 150 sacks. Top perforation 4093'. Bottom of the hole was sanded to
150', and cemented with 4 sacks through the dump bailer, with cement from 4050'
to 4000'. 2040' of 4 1/2" long string was recovered from the hole. Bridge plug was
pushed in fluid to 265', bridge plug and rock bridge from 265' to 255'. 8 sacks of
cement was mixed in a barrel, and put on plug at 255', through the dump bailer,
and let set over-night. Next day hole was ailed dry, and 17 sacks of cement was
added to plug, with cement from 255' to 180'. Hole was filled with mud to 40',
rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to
the base of the cellar.

I hereby certify that the above well was plugged herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 10/13/67

INV. NO. 66189-11