

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-075-20387-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Dome Petro # 5326

Complete Address Sydney Kans 67877

Lease Name Graben Coob Well No. A1

Location 1320' FSL - 20' FEL Sec. 25 Twp. 24 Rge. 41 (East)(West)

County Hamilton Total Depth 2458'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well was completed but not pro-

Plugging Contractor Midwest Casing Pulling

Address Box F Sublett Kansas 67877 License No. 6497

Operation Completed: Hour: 4:00 PM. Day: 21 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran 4 1/2" to 2458' cemented with 100 sbx of cement. They
plugged the 4 1/2" back to 2418' & perforated from 2410' to 17'.
1st plug 1 sbx bulls + 15 sbx of cement to cover perforations.
2nd plug at 1500' with 50 sbx of cement toping at 1300' covering
the gloe at the sand. 3rd plug at 300' with 30 sbx of cement.
4th plug 40' to 0' with 10 sbx of cement. The cement was
pumped through the 4 1/2" production pipe with hole full of
heavy mud. They recovered 1904' of 4 1/2" pipe. The plugging accomplished
Amount of Surface Casing: 8 5/8" at 250' cement circulated by Midwest Casing Pulling.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthis
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED
DATE 10-5-82
INV. NO. 1288-W