

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Livingston Oil Co.

Complete Address: Box 1797 Tulsa, Okla.

Lease Name Cook Well No. 25-41

Location C NW/4 Sec. 25 Twp. 24S Rge. 41 (E)/(W)

County Hamilton Total Depth 2380'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 8 PM Day 20 Month 11 Year 64

The Above well was plugged as follows:

7 5/8"-312' Circulated w/cement. 4 1/2"-2379' Circulated w/cement.

Top perforations 2362'. Plug bottom w/20 Sax.cement top cement 2150'

Mud 2150' to 350' Spotted 10 Sax.cement 350' to 250'

Mud 250' to 50' Plug; 5 Sax.cement 50' to 0

No pipe pulled. Company Pump. Cut surface & 4 1/2' off 5' below ground level.

I hereby certify that the above well was plugged as herein stated.

DATE 11/29/64

INV. NO. 202-10

Signed: [Signature]
Well Plugging Supervisor