

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1975

CONSERVATION DIVISION
Wichita, Kansas

10-31-75

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Tomlinson Oil Co. Inc.

Complete Address 200 West Douglas-Suite-1030. Wichita, Kansas 67202

Lease Name Boese Well No. # 2

Location N/2 NW NW Sec. 24 Twp. 22 Rge. (E) 2 (W)

County Harvey Total Depth 3481'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling. Allied Cementing Co.

Address Hutchinson, Kansas-Great Bend, Kansas License No. # 440

Operation Completed: Hour 3 PM Day 29 Month 10 Year 75

The above well was plugged as follows:

8 5/8"-276'-Circulated w/cement. 5 1/2"-3480'-Cemented. Bridge Plug-3442'.

Perf. 3430'. Sand hole to 3400'. 5 Sax. Cement at 3400'.

Allied Cementing Company pump 3 Sax. Hulls, 15 Sax. Gel, 75 Sax. Cement,

Plus 2% Gel. Hole filled to top. Pumping pressure at 500 Lbs.

Shut in pressure at 250 Lbs.

2600' - 5 1/2"-Pipe Pulled.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10/31/75

INV. NO. 9306-E