

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 11 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Barbara Oil Co.

Complete Address 509 Union Center Wichita, KS

Lease Name Cox Well No. 1

Location G NW/SE Sec. 26 Twp. 30 Rge. 10 (E) (W) W

County Kingman Total Depth 4545

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering Inc

Address Box 698 Great Bend, KS License No. 637

Operation Completed: Hour 11:00 AM Day 7 Month 12 Year 1972

The above well was plugged as follows:  
250 ft 8 5/8 surface pipe cemented with 200 sacks. 3226 ft 5 1/2 long  
string cemented with 125 sacks. Plug back at 2590 ft. Top perf.  
2564 ft. Sand to 2550 ft, 5 sacks cement with bailer. Pulled 2000  
ft 5 1/2. Set 10 ft rock bridge at 240 ft. with 25 sacks cement. Mud  
to 40 ft, 10 ft rock bridge, 10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 12/12/72  
INV. NO. 6715-4

Signed: [Signature]  
Well Plugging Supervisor