

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

WELL PLUGGING RECORD 15-009 - 03103-0000

Give All Information Completely  
 Make Required Affidavit

COUNTY Barton SEC. 28 TWP. 16s RGE. 11w E/W  
 Location as in quarters or footage from lines:  
NE SW NW


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Kaiser-Francis Oil Company  
 Lease Name Seyfert #2 Well No. \_\_\_\_\_  
 Office Address P.O. Box 35528, Tulsa, Okla. 74135  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 1/21/83  
 Plugging completed 1/28/83  
 Reason for abandonment of well or producing formation  
Depleted

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3376'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	254'	none
				5 1/2"	3367'	2290'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Plugged bottom with 5 sacks cement, sand to 3050', & ran 5 sacks cement.  
 Shot pipe at 2511', 2410', & 2312'. Pulled total of 72 joints. Plugged  
 well with 4 sacks hulls, 12 gel, 65 cement, 3 gel, 1 hull, plug, & 100  
 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 1983



RECEIVED  
 STATE CORPORATION COMMISSION  
 Notary Public.

My Commission expires: \_\_\_\_\_

FEB 14 1983

02-14-83

CONSERVATION DIVISION  
 Wichita Kansas

DRILLER'S LOG

COMPANY: Herman George Kaiser  
 Oil Producer  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: SEYFERT #2  
 LOCATION: NE SW NW Sec. 28-16-11  
 BARTON COUNTY, KANSAS  
 COMMENCED: 4-21-64  
 COMPLETED: 4-28-64

0	55	Surface Soil & Rock
55	254	Shale & Redbed
254	285	Shale
285	450	Dakota Sand
450	550	Shale
550	770	Redbed
770	805	Anhydrite
805	920	Redbed & Shale
950	1200	Shale & Redbed
1200	1605	Shale & Shells
1605	2075	Lime
2075	2495	Shale & Lime
2495	2525	Lime
2525	2670	Lime & Shale
2670	2935	Lime
2935	3080	Lime & Shale
3080	3376	Lime
	<u>3376</u>	<u>Rotary Total Depth</u> - Set 5 1/2" Casing

RECEIVED  
 STATE CORPORATIONAL COMMISSION  
 OCT 12 1982  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" surface casing @ 254' cemented with 175 sacks Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Seyfert #2 well, located NE SW NW of Section 28, Township 16, Range 11, Barton County, Kansas, as reflected by the files of Leben Drilling, Inc.

*Leslie Kite*  
 \_\_\_\_\_  
 Leslie Kite

STATE OF KANSAS )  
 ) ss  
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 29th day of April, 1964.

*Ulanda Nichols*  
 \_\_\_\_\_  
 Ulanda Nichols, Notary Public

My Commission Expires: April 1, 1967

HELOIS KOWEN  
 FLOREN COX  
 GEORGE COX  
 HOKINS  
 HULL & BULL  
 COLLIER & CO. INC.

**FILE COPY**

DISTRIBUTION: OFFICE OF REC. (L-6) STATE OF KANSAS