

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-230170000

LEASE NAME Norman Witt 1-30

WELL NUMBER 1-30

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

2970' Ft. from SYN Line of Section (circle one)

330' Ft. from EW Line of Section (circle one)

LEASE OPERATOR Parrish Corporation

SPOT LOCATION Se - Se - Ne

ADDRESS 110 So. Main, #510

SEC. 30 TWP. 22S S. RGE 12W (E) or (W)

CITY, STATE, ZIP Wichita, KS 67202

COUNTY Stafford

PHONE#(316)263 8726 OPERATORS LICENSE NO. 5228

Date Well Completed 12-04-95

Character of Well Dry and Abandoned
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 12-04-95

Date Plugging Completed 12-04-95

The plugging proposal was approved on 12-01-95 by Steve Middleton and on 12-03-95 by Steve Durrant (date)
by _____ (KCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation(s) _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULL OUT |
|-----------|---------|------|----|------|--------|----------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Spotted 100 sacks 60/40 Poz, 2% Gel, 1/4# Flowseal and 2% CC @ 2850' to 2950. WOC 3.5 hours.
Plug down @ 4m on 12-3-95 by Allied. Filled hole with mud to surface. Spotted 2nd plug at
710' with 50 sacks, 3rd plug @ 340' with 50 sacks, 4th plug @ 40' with 10 sacks using 60/40 Poz
with 6% Gel. Plugged rathole with 15 sacks.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company

License No. 5142

Address P.O. Box 1006 Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Parrish Corporation

STATE OF Kansas COUNTY OF Pratt, ss.

Steve E. McClain (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 1006 Pratt KS 67124


SUBSCRIBED AND SWORN TO before me this 29th day of December, 1995

Pamela S. Fields
Notary Public

My Commission Expires: 1-28-97

RECEIVED
STATE CORPORATION COMMISSION

JAN 02 1996



Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006

Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Norman Witt I-30

LOCATION: C Se Se Ne

Section 30 T 22S R 12W

API#: 15-185-230170000

Stafford County, Kansas

OWNER: Parrish Corporation (Burk & Williams)

COMMENCED: 28-Nov-95

CONTRACTOR: Sterling Drilling Company, Rig #4

COMPLETED: 04-Dec-95

TOTAL DEPTH: DRILLER 3198 FEET

LOGGER None FEET

LOG

| | | | |
|------|---|-----------|-------------------|
| 0 | - | 195 FEET | Top Soil and Sand |
| 195 | - | 313 FEET | Red Bed |
| 313 | - | 115 FEET | Clay and Shale |
| 115 | - | 1690 FEET | Shales |
| 1690 | - | 3198 FEET | Lime and Shale |

CASING RECORDS

SPUD @ 8:15 am on 11-28-95. Drilled 12-1/4" hole to 313'. Ran 7 joints of 8-5/8" new 23# surface casing. 298.19' set @ 310' KB. Cemented with 225 sx 60/40 Poz, 2% Gel, 3% CC. Plug down at 1:00 pm on 11-28-95 by Allied with good returns, Ticket # 4821.

Lost Circulation at 3198'. Squeezed 3 times and could not regain circulation.

Tripped in to plug well. Spotted 100 sacks 60/40 Poz, 2% Gel, 1/4# Flowseal and 2% CC at 2850'. Plug down @ 4:00 pm on 12-3-95 by Allied. WOC 3.5 hours then filled hole and tripped in with bit and tagged cement @ 2950'. Filled hole with mud.

Spotted 2nd plug @ 710' with 50 sacks. Spotted 3rd plug @ 340' with 50 sacks.

Spotted 4th plug @ 40' with 10 sacks.

Put 15 sacks in the rathole. Plug down @ 2:00 am on 12-4-95 by Allied. Ticket # 3783.

DEVIATION SURVEYS

3/4 DEG. @

313 FEET

RECEIVED
STATE OF KANSAS
REGISTRATION COMMISSION

JAN 02 1996

WICHITA, KANSAS

API 15-185-230170000

Norman Witt 1-30 Parrish Corporation

Proposed Method of Plugging (Cont'd): 4th plug spotted @ 40' with 10 sacks. Rathole plugged 15 sacks. (Plugs 2,3,4 &5 contained 60/40 Poz with 6% gel.

RECEIVED
STATE CORPORATION COMMISSION

JAN 0 2 1996

STATE CORPORATION COMMISSION
WICHITA, KANSAS