

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-21,500-0000

LEASE NAME Lewis #1

WELL NUMBER SW SW SW

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 31 TWP. 22s RGE. 12w (S) or (W)

COUNTY Stafford

Date Well Completed 3/8/82

Plugging Commenced 5/23/85

Plugging Completed 5/30/85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Dakota Resources, Inc.

ADDRESS 2900 Security Life Bldg., Denver Colo, 80202

PHONE#(303) 832-6450 OPERATORS LICENSE NO. 7107

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3845'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	259'	none
				4 1/2"	3845'	2279'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3450' & 4 sacks cement. Shot pipe at 3006', 2817', 2505', & 2279'. Pulled 54 joints of pipe. Plugged well with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug, & 125 sacks 60/40 poz 2% gel 3% c.c. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling STATE CORPORATION COMMISSION 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

RECEIVED
 JUN 15 1985
 6-5-85

R. Darrell Kelso

(Employee of Wichita Kansas or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 19 85

My Commission Expires:



Notary Public

Revis

15-185-21500-0000



Sonic Cement
Bond Log

FILING NO.	COMPANY <u>DAKOTA RESOURCES, INC.</u>
	WELL <u>LEWIS No. 1</u>
	FIELD _____
	COUNTY <u>STAFFORD</u> STATE <u>KANSAS</u>
Location <u>SW-SW-SW</u>	
Sec. <u>31</u> Twp. <u>22S</u> Rge. <u>12W</u>	
Other Services:	

Permanent Datum <u>GROUND LEVEL</u> Elev. <u>1856</u>	Elev.: K.B. <u>1861</u>
Log Measured From <u>KELLY BUSHING, 5</u> Ft. Above Perm. Datum	D.F. <u>-</u>
Drilling Measured From <u>KELLY BUSHING</u>	G.L. <u>1856</u>

Run No.	<u>ONE</u>	
Date & Time Survey	<u>3-13-82</u>	<u>9:00 AM</u>
Date & Time Cementing		
Type Cementing Operation	<u>PRIMARY</u>	
Depth Driller		
Depth Logger	<u>3794</u>	
Logged Interval	<u>3788</u> to <u>3100</u>	to
Casing Driller	@	@
Float Collar—D.V. Tool		
Squeeze Depth		
Amount & Type Cement		
Amount & Type Admix		
Type Fluid in Hole	<u>FRESH WATER</u>	<u>RECEIVED</u>
Fluid Level	<u>FULL</u>	STATE CORPORATION COMMISSION
Salinity PPM Cl	<u>N/A</u>	
Weight lb/gal—Vis.	<u>N/A</u> <u>N/A</u>	<u>MAR 13 1982</u>
Approx. Logged Cem. Top	<u>3296</u>	
Calculated Cement Top		CONSERVATION DIVISION
Max. Hole Temperature	<u>113° F</u>	°F. <u>W. PHILLIPS</u> °F.
Tool No.		
Spacing Recorded		
Equipment—Location	<u>38</u> <u>GREAT BEND, KS</u>	
Recorded by	<u>GARY WOOTEN</u>	
Witnessed by		

CASING RECORD
 Centralized Interval
 BORE HOLE RECORD