


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 North Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 21 Twp. 22S Rge. 16W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NE NE
Lease Owner Alpine Oil & Royalty Co., Inc.
Lease Name Klepper Well No. 1
Office Address 1100 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 21, 1957 19
Application for plugging filed December 21, 1957 19
Application for plugging approved December 21, 1957 19
Plugging commenced December 21, 1957 19
Plugging completed December 21, 1957 19
Reason for abandonment of well or producing formation non productive in commercial quantities
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edson Rutledge Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4117 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	684	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole with plug and 20 sacks cement at 300 feet.
Heavy mud to 40 feet, plug and holls and 10 sacks cement

12-27-57

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 1100 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson
1100 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1957

Virginia Mundell
Virginia Mundell Notary Public.

My commission expires August 10, 1961

PLUGGING
FILED SEC 21 T 22 R 16W
BOOK PAGE 72 LINE 17

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: December 9, 1957

Contractor: Quaker Drilling Co., Inc.

Completed: December 21, 1957

Alpine's Klepper No. 1
NW NE NE Section 21-22S-16W
Pawnee County, Kansas

Elevation: 2042 K. B.

Production: D. & A.

Casing Record:

Set 8 5/8 inch casing at 684 feet with 450 sacks pozmix

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Clay & Sand	113	Heebner	3498 -1456
Shale & Streaks of Sand	490	Brown Lime	3608 -1566
Soft Sand	570	Lansing	3617 -1575
Red Shale	590	Base of Kansas City	3877 -1835
Red Bgd & Blue Shale	684	Shaley Conglomerate	3937 -1895
Red Bed and Shells	830	Cherty Conglomerate	3964 -1922
Shale and Shells	1000	Simpson	4036 -1992
Red Bed and Shells	1032	Arbuckle	3074 -2032
Anhydrite	1064	Rotary Total Depth	4117 -2075
Shale and Shells	1875		
Shale and Lime	2050		
Hard Sandy Lime	2137		
Sandy Lime & Shale	2305		
Lime and Shale	2575		
Shale and Streaks of Sandy Lime	2735		
Shale and Lime	3310		
Sandy Lime and Shale	3385		
Shale and Lime	3780		
Hard Lime and Shale	3820		
Lime and Shale	3600		
Sandy Shale and Lime	3660		
Lime and Shale	4060		
Cherty Lime and Shale	4100		
Lime and Shale	4117		

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1957

CORPORATION DIVISION
JAN 2 1958

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NW NE NE of Section 21, Township 22 South, Range 16 West, Pawnee County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul

Thomas M. McCaul, President

SUBSCRIBED AND SWORN to before me a Notary Public in and for Sedgwick County, Kansas this 26th day of December, 1957.

MY COMMISSION EXPIRES:
August 10, 1961

Virginia Mundell
Virginia Mundell, Notary Public

PLUGGING	
WELL	SEC 21 T 22 R 16 W
BOOK	PAGE 72 LINE 17