

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Pawnee County, Sec. 11 Twp. 22 Rge. (E) 16(W)

Location as "NE/CNW%SW%" or footage from lines NW NW NE

Lease Owner Petroleum, Inc.

Lease Name Stumps Well No. 1

Office Address 305 East Third, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 4, 1953


Application for plugging filed July 4, 1953

Application for plugging approved July 4, 1953

Plugging commenced July 4, 1953

Plugging completed July 4, 1953

Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4060 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	214'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 300' and set wooden plug at 300'. Cemented and displaced 15 sacks cement through drill pipe onto plug at 300'. Mudded up to 210' and set second wooden plug at 210'. Cemented and displaced 25 sacks cement onto plug at 210'. Mudded up to 140' and set third wooden plug at 140'. Filled hole to bottom of well cellar with 10 sacks cement.

7-15-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Co.
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. W. Fisher

305 East Third, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of July, 1953

My commission expires October 13, 1954

Notary Public.



DRILLER'S LOG STUMPS NO. 1

Petroleum, Inc., Operator
Garvey Drilling Company, Contractor

Section 11, Twp. 22S, Rge. 16W

Location: NW NW NE

Drilling Commenced: June 23, 1953
Drilling Completed: July 4, 1953

County: Pawnee County, Kansas

R.T.D.: 4060

Casing Record: 8 5/8" @ 214' w/175 sax

Production: D & A

Figures below indicate bottom of formation:

70 Sand
90 Shale
95 Sand
450 Shale & Shells
535 Sand
990 Red Sale
1020 Anhydrite
1960 Shale & Shells
2010 Lime & Shale
2355 Lime
3290 Lime & Shale
4060 Lime

Tops:

Heebner: 3447 (-1439)
Brown Lime: 3554 (-1546)
Lansing: 3563 (-1555)
Conglomerate: 3898 (-890)
Simpson: 3959 (-1951)
Arbuckle: 4027 (-2019)

4060' R.T.D.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W W Fink

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS)

COUNTY OF SEDGWICK)

JUL 15 1953
SS: CONSERVATION DIVISION
Wichita, Kansas

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 8th day of July, 1953.

Charlotte Heiden
Notary Public

My commission expires: October 13, 1954.

PLUGGING
FILE SEC 11 T 22 R 16W
BOOK PAGE 112 LINE 32