


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Kingman County, Sec. 2 Twp. 30S Rge. 10 (W) (X) 10 (W)
Location as "NE/CNW/SW" or footage from lines C NE NE
Lease Owner George Ablah
Lease Name Simon Well No. 1
Office Address 8028 Cork, Wichita, Kansas 67206
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 20 1973
Application for plugging filed October 20 1973
Application for plugging approved October 20 1973
Plugging commenced October 20 1973
Plugging completed October 20 1973
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 2530 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	216 1/2'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 200 feet. Followed by wooden plug, 1/2 sack hulls and placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Betty Brandt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt
505 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of October, 1973

Mercedes Dobbins
Mercedes Dobbins Notary Public.

My commission expires
MERCEDES DOBBINS
STATE NOTARY PUBLIC
Sedgewick County, Kansas
My Commission Expires
February 11, 1976

ROTARY DRILLERS' LOG

OPERATOR: George Ablah DRILLING COMMENCED: October 16, 1973
 8028 Cork
 Wichita, Kansas 67206

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: October 20, 1973
 505 Union Center
 Wichita, Kansas 67202

CASING RECORD: 5 Jts. 216½' 8-5/8" LOCATION: Simon No. 1
 cemented with 250 sacks " C NE NE
 "Section 2-30S-10W
 Kingman County, Kansas

0 - 25 Sod
 25 - 70 Sand
 70 - 360 Red bed
 360 - 1250 Shale & shells
 1250 - 1640 Lime & shale
 1640 - 1965 Shale & lime
 1965 - 2230 Lime with shale
 2230 - 2530 Lime & shale
 2530 Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 24 1973
 CONSERVATION DIVISION
 Wichita, Kansas


I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Petty Brandt
Secretary-Treasurer

STATE OF KANSAS)
) ss.
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 23rd of October, 1973.



Mercedes Dobbins
Mercedes Dobbins Notary Public