

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail on Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Pawnee County. Sec. 19 Twp. 22S Rge. (E) 18(W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Graham-Messman-Rinehart Oil Company
Lease Name Higgins "A" Well No. 1
Office Address 1005 East Second Street, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed August 15, 1954 19
Application for plugging filed August 15, 1954 (Verbal) 19
Application for plugging approved August 15, 1954 (Verbal) 19
Plugging commenced August 15, 1954 19
Plugging completed August 15, 1954 19
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4698 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bottom plug at 250' with 20 sacks cement. Set top plug at 40' with 10 sacks cement to within 10' of surface. Mud to surface.

Rec'd 8-15-54

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graham-Messman-Rinehart Oil Company
Address 1005 East Second Street, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
1005 East Second St., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of September, 19 54

Notary Public.

My commission expires September 14, 1957

PLUGGING
FILE SEC 19 T 22 R 18 W
BOOK PAGE 56 LINE 35

NO. 1 HIGGINS "A"WELL RECORD

Location: NE NE SW 19-22S-18W
Pawnee County, Kansas

Commenced: July 30, 1954

Completed: August 15, 1954

Operator: Graham-Messman-Rinehart Oil Company
1005 East Second, Wichita, Kansas

Elevation: 2110 KB

Contractor: Graham-Messman-Rinehart Oil Company
1005 East Second, Wichita, Kansas

Production: D & A

Casing Record: 8 5/8" @ 255' w/175 sacks cement

....L O G....

Clay	126
Sand	190
Shale	625
Red sand	747
Shale	1750
Lime - shale	2035
Shale - lime	2285
Lime - shale	2392
Lime	2595
Shale - lime	2816
Lime - shale	3234
Lime	3772
Kansas City	3823
Lime	4161
Lime - Shale	4265
Lime	4325
Chert	4346
Lime	4417
Lime - chert	4457
Shale - lime - sand	4470
Shale - sand	4478
Lime - chert	4591
Chert - lime	4619
Lime - chert	4678
Lime - Arbuckle	4698 RTD

Heebner 3680 (-1570)
Brown Lime 3765 (-1655)
Lansing 3775 (-1665)
Conglomerate 4270 (-2160)
Mississippi 4296 (-2186)
Kinderhook 4350 (-2240)
Viola 4468 (-2358)
Simpson 4602 (-2492)
Arbuckle 4648 (-2538)

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By: J. N. Gilliland

J. N. Gilliland

Subscribed and sworn to before me this 2nd day of September, 1954.

Betty June Bayles
Notary Public

Commission Expires: September 14, 1957

PLUGGING

FILE SEC 19 T 22 R 18W
BOOK PAGE 56 LINE 35