

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202  
NORTH

WELL PLUGGING RECORD

Pawnee County. Sec. 16 Twp. 22S Rge. 18W ~~6E~~ ~~XXX~~  
Location as "NE/CNW&SW" or footage from lines SW NW NW  
Lease Owner Tcer Addis  
Lease Name Earl Meckfessel Well No. 1  
Office Address P.O. Box 519 - Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 4, 19 71  
Application for plugging filed Verbal Application 19  
Application for plugging approved Verbal Approval 19  
Plugging commenced June 4, 19 71  
Plugging completed June 4, 19 71  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,207 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1,150'	None
RECEIVED STATE CORPORATION COMMISSION JUN 14 1971 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,207 feet (rotary total depth) to 420 feet. Set plug at 420 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud from 420 feet to 10'. Set solid plug at 10 feet and cemented to cellar with 10 sacks cement, 2 sacks cement in rathole.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor H-30, Inc.  
Address 200 North Main - Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Dean Britting, Agent (~~employee of owner~~) or (~~owner or operator~~) of the above-described

well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 North Main - Wichita, Kansas 67202  
(Address)

Subscribed and Sworn to before me this 10th. day of June, 19 71

My commission expires June 30, 1974  
Elsie Willison Notary Public.



15.145-20217-0000

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **Icer Addis**  
FARM **Earl Meckfessel** NO. **1**

SEC. **16** T. **22S** R. **18W**  
LOC. **SW NW NW**

TOTAL DEPTH **4,207'**  
COMM. **May 26, 1971**  
SHOT OR TREATED  
CONTRACTOR **H-30, Inc.**  
ISSUED

COMP. **June 4, 1971**

COUNTY **Pawnee**  
KANSAS



CASING  
20 10  
15 8-5/8" 1,150' cemented w/525 sxs cement  
12 6  
13 5  
ELEVATION **2,061 KB**  
PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	20'
Shale	40'
Shale and Sand	75'
Shale	575'
Sand	585'
Shale and Redbed	1,136'
Anhydrite	1,166'
Shale	1,926'
Shale and Lime	2,100'
Lime and Shale	2,400'
Shale and Lime	3,065'
Lime and Shale	3,275'
Lime	3,455'
Lime and Shale	3,761'
Lime	4,158'
Sand and Lime	4,173'
Lime and Chert	4,207'
Rotary Total Depth	4,207'

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 14 1971  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
\_\_\_\_\_  
Dean Britting

State of Kansas }  
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public  
and for said county and state this 10th. day  
of June, 1971.

*Elsie Willison*  
\_\_\_\_\_  
Elsie Willison-Notary Public

My Commission Expires:  
June 30, 1974

