


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Flat

Pawnee County. Sec. 16 Twp. 22 Rge. 18 (E) (W)
 Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW NW
 Lease Owner Great Bend Pipe & Supply
 Lease Name Meckfessel Well No. 1
 Office Address West 10th, Gt. Bend, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Oil
 Date well completed 1948 19
 Application for plugging filed June 25, 1955 19
 Application for plugging approved June 27, 1955 19
 Plugging commenced June 28, 1955 19
 Plugging completed June 30, 1955 19
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Horner
 Producing formation Mississippi chat Depth to top 4160 Bottom 4375 Total Depth of Well 4500 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|------------|---------|------|----|-------|--------|------------|
| Miss. chat | 175 sx | | | 8 5/8 | 215 | none |
| | 175 sx | | | 5 1/2 | 4375 | 3185 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled from 4500' to 4145' with sand
 5 sx cement at 4145
 pumped 20 sx M Jell mud
 and 20 sx M weight mud
 100 sx bulk cement
 Filled top of surface pipe with cement 15 sx

Mr. Horner was at well until well was plugged

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Gt. Bend Pipe & Supply
 Address Box 414 Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
 Nathan Meltzer
 (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
 (Signature) *Nathan Meltzer*
 Gt. Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 1955

My commission expires 3-30-57 *Anne Meltzer* Notary Public.

23-5091-3 8-50-10M

PLUGGING
 FILE SEC 16 T 22 R 18W
 BOOK PAGE 130 LINE 3

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 5 - 1955 7-5-55
 CONSERVATION DIVISION
 Wichita, Kansas

15-145-00309.000 0

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Gl. Head P & S Co.

Company WELCH & OLSSON DRILLING CO., INC.
Farm Meckfessel No. 1

SEC. 16 T. 22 R. 18W
NW NW NW

Total Depth. 4540

Comin. 4-9-55

Comp. 4-24-55


Shot or Treated.

Contractor. Welch & Olsson Drilling Co., Inc.

Issued. 8-6-55

County Pawnee

KANSAS



Elevation. 2058 RB

Production Phys. Pot. 11 BOPD

Figures Indicate Bottom of Formations.

| | |
|---------------------|------|
| red bed & shale | 565 |
| sand | 675 |
| shale | 850 |
| anhydrite | 1155 |
| shale & shells | 1940 |
| lime & shale | 2715 |
| shale & shells | 3117 |
| shale & lime | 3395 |
| lime | 3495 |
| lime & shale | 3610 |
| lime | 4160 |
| conglomerate sand | 4170 |
| lime & chert | 4223 |
| shale | 4241 |
| shale, chert & lime | 4260 |
| shale & chert | 4300 |
| shale, chert & lime | 4390 |
| sand | 4415 |
| shale & lime | 4430 |
| lime | 4540 |
| Total Depth | |

TOPS:

| | |
|---------------------|------|
| Anhydrite | 1130 |
| Heebner | 3584 |
| Brown lime | 3673 |
| Lansing-KC | 3680 |
| Cherty conglomerate | 4150 |
| Viola | 4316 |
| Simpson | 4449 |
| Arbuckle | 4497 |

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 X 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
WEL SEC 16 T 22 R 18W
BOOK PAGE 130 LINE 3