

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Pawnee County, Sec. 17 Twp. 22 Rge. 18 (E) (W)

Location as "NE/CNW&SW&" or footage from lines. SE NE NE
Lease Owner Addis Oil Operations
Lease Name Meckfessel #1 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/16/71 19____
Plugging completed 6/19/71 19____
Reason for abandonment of well or producing formation depleted.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4204 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1147'	none
				5 1/2"	4202'	3610'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4204', ran sand to 4150' and dumped 5 sacks of cement.
Loaded hole, shot pipe at 3669', 3603', worked pipe loose and pulled
112 joints. Mudded to 425', set rock bridge to 400' and ran 6 ards of
ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

Sworn to before me this 7th day of July, 1971
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975
Margaret Melcher
Notary Public.



JUN 16 1971
 CONSERVATION DIVISION
 Wichita, Kansas

WELL LOG

DATE COMMENCED: January 23, 1971
 DATE COMPLETED: February 2, 1971

Icer Addia
 MECKFESSEL #1
 SE/4 NE/4 NE/4
 Sec. 17-T22S-R18W
 Pawnee County, Kansas

ELEVATION: 2062 K.B.

0	-	65'	Clay
65	-	195'	Shale & Clay
195	-	360'	Shale w/sand streaks
360	-	440'	Shale & Red Bed
440	-	470'	Hard Sand
470	-	685'	Sand & Shale streaks
685	-	1132'	Red Bed
1132	-	1163'	Anhydrite
1163	-	1415'	Red Bed
1415	-	1440'	Sand
1440	-	1855'	Red bed-Shale & sand streaks
1855	-	1930'	Shale & Shells
1930	-	2420'	Lime & Shale
2460	-	2790'	Shale
2790	-	3463'	Lime & Shale
3463	-	3470'	Lime & Chalk
3470	-	3600'	Lime & Shale
3600	-	3605'	Shale
3605	-	3620'	Lime & Shale
3620	-	3629'	Lime
3629	-	3686'	Shale
3686	-	3696'	Lime & Shale
3696	-	4143'	Lime
4143	-	4167'	Conglomerate
4167	-	4177'	Cher. Sand
4177	-	4203'	Lime
		4203'	RTD

FORMATION DATA

ANHYDRITE	1132
HEEDNER	3600
TORONTO	3620
DOUGLAS	3629
BROWN LIME	3686
KANSAS CITY	3696
CONGLOMERATE	4143
CHER. SAND	4167
RTD	4203

SURFACE CASING: Set 1147'
 of new 8-5/8" 20# casing
 cemented with 525 sacks
 cement.

PRODUCTION CASING: Set
 new 5 1/2" casing at 4202'
 with 100 sacks 60/40 salt
 br. pozmix.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts
 and statements herein contained are true and correct to the best of
 his knowledge.

Larry Curtis
 Larry Curtis

Subscribed and sworn to before me this 8 day of February 1971

My Comm. Expires:
April 11, 1974

Maureen M. Hagan
 Notary Public