

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee

~~XXXXXX~~

County, Sec. 17 Twp. 22 Rgs. 18 (X) (W)

Location as "NE/CNW/SW" or footage from lines NW/4 NE/4 NE/4

Lease Owner Al Tipton

Lease Name MECKEESSEL Well No. 1

Office Address Box 157, Hays, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 3, 1972 19 72

Application for plugging filed " " 19 72

Application for plugging approved " " 19 72


Plugging commenced August 3, 1972 19 72

Plugging completed " " 19 72

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4236 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full of heavy mud -
Set Plug @ 400' w 25 sacks cement thru drill pipe
Top Plug set at 40' with 1/2 sack hulls & 12 sacks cement
2 sacks cement in rat hole

8-7-72

RECEIVED
STATE CORPORATION COMMISSION
AUG 7 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson

Box 823-Great Bend, Ks. 67530

(Address)

SUBSCRIBED AND SWORN to before me this 4th day of August, 19 72.

My commission expires 4-11-1974

Martha M. Gagne
Notary Public.

W E L L L O G

Date Commenced: July 24, 1972
 Date Completed: August 3, 1972

A1 Tipton
 MECKFESSEL #1
 NW/4 NE/4 NE/4
 Sec. 17-22-18w
 Pawnee County, Kansas

ELEVATION: 2064 K.B.

0	-	60'	Clay
60	-	185'	Shale & Clay
185	-	410'	Sand streaks & shale
410	-	745'	Sand and shale
745	-	1140'	Red Bed
1140	-	1172'	Anhydrite
1172	-	1350'	Red Bed
1350	-	1955'	Shale & Shells
1955	-	3607'	Lime & Shale
3607	-	3612'	Shale
3612	-	3623'	Shale & Lime
3623	-	3637'	Lime
3637	-	3691'	Shale
3691	-	3701'	Lime, br.
3701	-	3996'	Lime
3996	-	4098'	Lime & Shale
4098	-	4119'	Lime
4119	-	4185'	Shale
4185	-	4218'	Chert
4218	-	4236'	Shale
4236	-		RTD

FORMATION DATA

Anhydrite	1140
Heebner	3607
Toronto	3623
Douglas	3637
Brown Lime	3691
Kansas City	3701
Base K.C.	3996
Fort Scott	4098
Cherokee Shale	4119
Mississippi	4185
Kinderhook	4218
RTD	4236

SURFACE PIPE: Set 1157'
 of 8-5/8", 20# new pipe with
 425 sacks cement.

~~XXXXXXXXXXXXXXXXXXXX~~

RECEIVED
 STATE CORPORATION COMMISSION
 10-7-1972
 CONSERVATION DIVISION
 Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss.

Leonard Williamson of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 4th day of August 1972.

My Comm. Expires: April 11, 1974

Dorothy M. Hagar
 Notary Public