

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee

County, Sec. 7 Twp. 22 Rge. 19 ~~XEX~~ (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE

Lease Owner Solar Oil Company

Lease Name Anna Harnish Well No.

Office Address 1117 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 18, 19 55

Application for plugging filed May 18, 19 55

Application for plugging approved May 18, 19 55


Plugging commenced May 18, 19 55

Plugging completed May 18, 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Warren Horner, Great Bend, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4670 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	975.79	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4670 feet to surface feet for each plug set.

Plug and 1/3 sack hulls 20 sacks cement pumped through drill pipe at 300 feet.
Plug and 1/3 sack hulls 10 sacks cement at 35 feet.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D. & M. Drilling Company, Inc.

Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

James Davis, Jr. Employee of owner or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Davis, Jr.

(Address)

SUBSCRIBED AND SWORN to before me this 19th day of May, 1955.

My commission expires July 27, 1955

Leota Lee Miller Notary Public.

PLUGGING
FILED SEC 7 T 22 N 19 W
BOOK PAGE 120 LEE 42

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1955
5-27-55
CONSERVATION DIVISION

HARNISH #1

NE/4 NE/4 NE/4 of Section 7-22S-19W Pawnee County, Kansas

Rigged up Rotary Tools 4/29/55

Tore Down Rotary Tools 5/18/55

Ran 32 Jts (975.15') 8-5/8 - 32# 8 Rd Thd
Class "B" Pipe set @ 973'. Cemented with
250 sacks cement, 1% Cal. Cl.; 250 sacks
cement, 2% Gel, 1% Cal. Cl.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Clay & sand	0'	40'
Shale w/lime shells	40	380
Sand (hard)	380	470
Sand & shale	470	575
Shale & shells	575	685
Sand	685	735
Shale, shells & redbed	735	974
Shale & redbed	974	1225
Anhydrite	1225	1265
Shale & shells	1265	1474
Shale & salt	1474	1550
Shale	1550	1775
Lime & shale	1775	1875
Lime, sand & shale	1875	2080
Lime & sand	2080	2110
Shale w/lime streaks	2110	2209
Lime w/shale streaks	2209	2377
Lime & sand w/shale streaks	2377	2450
Lime & sand w/shale streaks	2450	2545
Lime, sand & chert	2545	2605
Lime & sand	2605	2796
Lime & shale	2796	2924
Lime w/shale streaks	2924	3173
Lime & shale	3173	3499
Lime	3499	3763
Lime w/some chert	3763	3787
Lime & chert	3787	3815
Lime	3815	4098
Lime & shale	4098	4297
Conglomerate	4297	4337
Lime & chert	4337	4384
Chert	4384	4410
Lime & chert	4410	4443
Lime, shale, dolomite & sand	4443	4495
Lime, dolomite, sand & chert	4495	4515
Lime & chert	4515	4558
Lime, dolomite & shale	4558	4582
Lime, shale & chert	4582	4625
Lime	4625	4670 TD

I, Don S. Packer, do hereby certify that the foregoing log is true and correct,
to the best of my knowledge and belief.

Don S. Packer
Don S. Packer

Subscribed and sworn to before me this 18th day of May, 1955

Leota Lee Miller
Leota Lee Miller

My commission expires: July 27, 1955

PLUGGING
FILE SEC 7 T 22 R 19W
BOOK PAGE 120 LINE 42

REC
STATE COMMISSION
MAY 25 1955
CONSERVATION DIVISION
Wichita, Kansas