

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 22 TWP. 22S RGE. 19W E/W
Location as in quarters or footage from lines:
1980' FSL & 1980' FEL

Lease Owner Maguire Oil Company
Lease Name Lippoldt #1 Well No. _____
Office Address 4200 First Nat'l Bank Bldg. Dallas, Texas 75202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 1-6-82
Plugging completed 1-9-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom _____ T.D. 4800'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	877'	none
				5-1/2"	4432'	2293'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

~~Pumped 25 sacks gel, and 25 sacks weight mud down surface pipe. Shot casing @3770' 3520', 3308', 2893', 2514' and 2304'. Pulled a total of 55 joints of pipe. Plugged well with 7 sacks gel, 3 sacks hulls, 5 sacks gel, 70 sacks 50/50 pos, 4% gel, 3% cc., 10 sacks gel, 8-5/8" plug, 70 sacks 50/50 pos, 4% gel, 3% cc. Plugging Completed.~~

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 82

My Commission expires:



Irene Hoover
STATE CORPORATION Notary Public.

JAN 14 1982 1-14-82