


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Pawnee County. Sec. 14 Twp. 22S Rge. (E) 17 (W)  
Location as "NE/CNW/SW" or footage from lines C NW NW  
Lease Owner Alpine Drilling Co., Inc.  
Lease Name Johnson Well No. B #1  
Office Address 800 Bitting Building, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed July 4, 1971 19  
Application for plugging filed July 4, 1971 (by phone) 19  
Application for plugging approved July 4, 1971 (by phone) 19  
Plugging commenced July 4, 1971 19  
Plugging completed July 4, 1971 19  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4060 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1065	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

First plug set at 400 feet with 30 sacks cement through drill pipe. Filled to 40' with mud.  
Second plug at 40 feet with 1/2 sack hulls, 10 sacks cement.  
Bridged the rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Gabbert-Jones, Inc.  
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Jon T. Williams, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jon T. Williams, Jr.  
800 Bitting Bldg., Wichita, Kansas 67202  
(Address)

Sworn to before me this 4th day of July, 19 71

Evelyn Wanko  
Evelyn Wanko Notary Public.



GABBERT-JONES, INC.  
 WICHITA, KANSAS  
DRILLERS' WELL LOG

JOHNSON B#1  
 C NW NW Sec. 14-22S-17W  
 Pawnee County, Kansas

Commenced: June 24, 1971  
 Completed: July 4, 1971

OPERATOR: Alpine Drilling Co. Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	40	Sand and Shale	Ran 27 joints used 8 5/8" 28#
40	470	Shale and Sand	casing set @ 1065' w/200 sks
470	588	Sand	60/40 Posmix 4% gel 3% CC and 225 sks
588	1057	Redbed and Shale	Common 2% gel and 3% CC
1057	1068	Anhydrite	P.D. @ 6 PM 6/25/71
1068	1075	Lime	Cement Circ. Job by Allied
1075	1077	Anhydrite	
1077	1700	Shale and Shells	
1700	2056	Shale and Lime	
2056	2335	Lime and Shale	
2335	2495	Shale and Lime	
2495	2810	Lime and Shale	
2810	2995	Lime	
2995	3205	Lime and Shale	
3205	3318	Lime	
3318	3335	Lime and Shale	
3335	3420	Lime	
3420	3610	Lime and Shale	
3610	3720	Lime	
3720	3790	Lime and Shale	
3790	3940	Lime	
3940	4005	Lime and Chert	
4005	4045	Shale and Lime	
4045	4060	Lime and Shale	
4060		T.D.	DRY & ABANDONED

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 12 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the C NW NW, Sec. 14-22S-17W, Pawnee County, Kansas, to the best of my knowledge and belief.

*James S. Sutton II*  
 James S. Sutton II

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 8th day of July, 1970, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

*Marjorie Hall*  
 Marjorie Hall, Notary Public

My commission expires Nov. 29, 1971