


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County, Sec. 27 Twp 16 Rge. 11 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SE NW  
Lease Owner Hinkle Oil Company  
Lease Name Wellenberg Well No. 2  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 11/21/67 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 11/29/67 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3387 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	105'	none
				5 1/2"	3383'	1979'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked bottom, ran sand to 3360' and dumped 5 sacks of cement.  
Shot pipe at 2782', 2679'. Hooked up pump to spot oil. Pumped 50  
barrels oil, chased plug to 2700'. Pumped 4 sacks hulls, 8 sacks gel and  
pumped 70 barrels oil, chased plug to 2700', worked pipe, got 16"  
tension, let pipe set on tension. Shot pipe at 1980', worked pipe  
loose and pulled 66 joints. Allied pumped 25 sacks gel and 125 sacks  
of cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 19 1968

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY, INC.  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of November, 19 67

My commission expires February 15, 1971

Margaret Melcher  
Notary Public.

Casing Record:

10" 105' w/125 sx  
 5½" 3383' w/100 sx

Willengerg #2 SW SE NW  
 Sec. 27-16S-11W, Barton County,  
 Kansas, Owners: Gulf Oil Corp.  
 & Hinkle Oil Company  
 Contractor: Hinkle Oil Company  
 Elevation: 1929'

Commenced: 2-4-45

Completed: 2-25-45

0	34	Clay & Gravel.
34	105	Lime & Shale
105	290	Shale
290	365	Sand
365	1065	Shale & Shells
1065	1225	Shale & Salt
1225	1310	Shale & Shells
1310	1445	Shale
1445	1705	Shale & Lime
1705	1730	Shale
1730	1765	Lime
1765	1775	Sand
1775	2015	Lime
2015	2368	Shale & Lime
2368	2464	Lime
2464	2755	Lime & Shale
2755	2975	Lime
2975	3077	Lime & Shale
3077	3330	Lime
3330	3361	Lime & Shale
3361	3387	Lime
3387		TD

Tops:

KC	3089
Conglomerate	3362
Arb. Dolomite	3382


State of Kansas )  
 County of Sedgwick ) SS

I hereby certify that the above is true and a correct log as compiled from the daily drilling reports kept on said well.

*Orvie Howell*  
 Orvie Howell

Subscribed to before me this 13th day of November, 1967

*Fred E. Kunkle Jr.*  
 Fred E. Kunkle, Jr.



My Commission Expires September 19, 1971

RECORDED  
 STATE OF KANSAS  
 NOV 15 1967  
 COUNTY OF SEDGWICK