


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-009-03084-0000

NORTH



Locate well correctly on above  
Section Plat

Barton County, Sec. 27 Twp. 16 Rge. 11 (E) W (W)  
Location as "NE/CNW&SW" or footage from lines N/2 NW SW  
Lease Owner Hinkle Oil Company  
Lease Name Burmister Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 6-12-64 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 6-13-64 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3369 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<del>10"</del>	<del>107'</del>	
				10"	107'	None
				5-1/2"	3357'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3369', sanded hole to 3350' and  
dumped 5 sacks of cement @ 3350' with dump bailer.  
Pumped 20 sacks of cement to surface pipe and 20  
sacks of cement to 5 1/2" casing to fill 5 1/2" to surface.  
Pumped 5 sacks of ~~cement~~ cement to surface  
pipe and filled to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 23 1964

PLUGGING COMPLETE.

07-23-64  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 19 64

My commission expires May 20, 1968

Milton J. Volin  
Notary Public.

casing record.  
10" 107'  
5" 3357'

Burmeister EB. 1. GN $\frac{1}{2}$  NW SW 27-16-11  
330' S NL 660' E WL NW SW  
Owners Hinkle Oil Company & Gulf Oil Corporation.  
Comm. 1-24-40 Comp. 2-15-40 Oct. 22/42

surface	107
shale	260
sand	340
shale	479
sand	515
red rock and shale	760
lime	787
shale and shells	1200
salt	1320
shale and shells	1500
lime	2685
red rock	1700
cherty shale	1775
lime	1805
cherty lime shale	1830
lime	1861
shale	1885
lime	2157
shale	2214
lime & shells	2340
shale	2390
lime	2410
shale	2500
lime	2561
shale & sand	2677
broken lime	2690
shale	2730
lime & shells	3064
shale	3070
lime	3174
shale	3177
lime soft & shale	3221
lime	3357
Arbuckle lime	3365

Top of Arbuckle 3357  
Cored from 3359 to 3363 Full recovery 100% saturation.  
First oil showing 3357  
hole filled 3000' from 3-15 PM to 5-50 PM.

**RECEIVED**  
STATE CORPORATION COMMISSION  
AUG 12 1964  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

HINKLE OIL COMPANY  
*Orvie Howell*  
Orvie Howell, Geologist

Subscribed and sworn to before me this 11th day of August 1964.

*Muriel A. Upton*  
Muriel A. Upton, N. P.

My commission expires 1-17-66