


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Harvey County, Sec. 31 Twp. 22 Rge. 2W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE NW NW
Lease Owner Sanders Oil Co.
Lease Name Furnish #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6/3/80 19
Plugging completed 6/9/80 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Thompson
Producing formation Depth to top Bottom Total Depth of Well 3250
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	213	none
				1 1/2"	3249	2436'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 3100' and ran 4 sacks cement. Shot pipe at 2447', pulled 67 joints.
Bailed hole to 225', set rock bridge from 225 to 215' and ran 3 1/2 yards ready mix.

PLUGGING COMPLETE.

6-16-80

RECEIVED
COMMISSION
JUN 16 1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of June, 19 80

Margaret Melcher
Notary Public.

My commission expires



WELL LOG

15-079-20339-0000

Operator Chas. W. Sanders Oil Co.
 Comm Comp
 Shot Qts. From ft. To ft.
 Acidized Gal.
 Prod. Formation _____
 Initial Prod _____
 Elevation _____

Lease Furnish Well No. 1
 Loc NE NW NW Sec 31 Twp 22 Rge 2W
 County Harvey State Kansas
 Contractor Triangle Drilling

Casing Record			
Size	Ft.	Pulled	Remarks
8 - 5/8	213	145	sk's cement
4 - 1/2	3249	150	sk's cement

FIGURES INDICATE BOTTOM OF FORMATION

0	213	Surface
213	485	Shale
485	1230	Shale & Lime
1230	1446	Shale
1446	1706	Shale
1706	1932	Lime & Shale
1932	2075	Shale & Lime Stks
2075	2349	Shale
2349	2520	Shale & Lime
2520	2636	Lime
2636	2930	Lime
2930	3078	Lime & Shale
3078	3142	Shale & Lime
3142	3157	Miss
3157	3250	Miss RTD

Geologist Report page 211 8 5/8"

*Perforations
 3157 - 3158
 3162 - 3163
 3180 - 3183*

Plug back 3248'

RECEIVED
 OIL AND GAS COMMISSION
 APR 28 1960
 CONSERVATION DIVISION
 Topeka, Kansas