


WELL PLUGGING RECORD

Gives All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 30 Twp. 22S Rge. (E) 22(W)
Location as "NE/CNW/SW" or footage from lines: C NW SE
Lease Owner: Pickrell Drilling Company
Lease Name: Housman "C" No. 1
Office Address: 705 4th National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole
Date well completed: March 18, 1964
Application for plugging filed: March 18, 1964
Application for plugging approved: March 18, 1964
Plugging commenced: March 18, 1964
Plugging completed: March 18, 1964
Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Frank Broadfoot
Producing formation: Depth to top: Bottom: Total Depth of Well: 4593 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	274'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 270'. Set plug. Cemented with
15 sacks cement. Heavy mud to 45'. Set plug.
Cemented with 15 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

Handwritten: Reed 4-1-64

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Pickrell Drilling Company
Address: 705 4th National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) C. W. Sebits
705 4th National Bank Bldg, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of March, 1964
Maxine Blackman
Notary Public.
My commission expires June 21, 1966

ROTARY DRILLING LOG

COMPANY, PICKRELL DRILLING COMPANY
705 4th National Bank Building
Wichita 2, Kansas

Rotary Drilling Commenced 3--5-64Rotary Drilling Completed 3-17-64

LOCATION: Housman "C" No. 1, C NW SE Sec. 30-22-22W, Hodgeman
County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (13 jts) 8 5/8" surface casing set at 274', cemented with 170
sacks cement. Circulated. Completed 5:15 P.M. March 5, 1964.
No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

75	Post Rock	
620	Shale & Shells	<u>C. F. S.</u>
775	Red Beds & Shale	4345
855	Red Beds	4355
870	Blaine	4393
950	Red Beds, Shale & Shells	4503
1165	Sand	4507
1475	Shale & Shells	4577
1510	Anhydrite	4583
2070	Shale & Shells	4589
2130	Lime & Shale	4593
2270	Shale & Lime, Shells	
2430	Lime & Shale	
2790	Lime	<u>Slope Tests</u>
2860	Lime & Shale	2500
2950	Lime	3000
3705	Lime & Shale	3500
3735	Sandy Lime & Shale	4000
3755	Lime & Shale	
3825	Shale, Sand & Lime	
3956	Lime & Shale	<u>S. L. M.</u>
4095	Lime	3959
4140	Lime & Shale	4387
4406	Lime	
4507	Lime & Shale	
4517	Lime	
4557	Lime & Shale	
4571	Conglomerate	
4583	Mississippian	
4593	Mississippian Chert - RTD	

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1964

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS

COUNTY OF SEDGWICK } ss.:

On this 24th day of March, 1964, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman Notary Public