

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-21,383-0000

LEASE NAME Webster

WELL NUMBER 1

2310 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 36 TWP. 22S RGE. 22 (E/W) (W)

COUNTY Russell

Date Well Completed 9/1/92

Plugging Commenced 9/1/92

Plugging Completed 9/1/92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR National Petroleum Reserves, Inc.

ADDRESS 250 N. Rock Rd., Suite #340, Wichita, KS 67206

PHONE#(316) -681-3515 OPERATORS LICENSE NO. _____

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-1-92 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4580'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	323'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4580'-1480' 10 sks cement @ 40'
50 sks cement @ 1480' 15 sks in rathole
50 sks cement @ 775' 10 sks in mousehole
50 sks cement @ 340'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506 9-4-92

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: National Petroleum Reserves, Inc.


STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506



SUBSCRIBED AND SWORN TO before me this 2nd day of September, 1992

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

My Commission Expires: 2-6-96

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1992
CONSERVATION DIVISION
Wichita, Kansas

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: National Petroleum Reserves, Inc.
250 N. Rock Rd., Suite #340
Wichita, Kansas 67206

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Webster

WELL #1

LOCATION: SW SE NE
Section 36-22S-22W
Hodgeman County, Kansas

ROTARY TOTAL DEPTH: 4580'

ELEVATION: 2308' K.B.

COMMENCED: 8/24/92

COMPLETED: 9/1/92

CASING: 8-5/8" @ 323' w/195 sks cement

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Shale	325'	Lime & Shale	3610'
Cedar Hills	895'	Shale	3838'
Red Bed	1112'	Lansing	4035'
Anhydrite	1458'	Marmaton	4355'
Red Bed	1489'	Ft. Scott	4485'
Shale	1990'	Mississippi	4575'
Lime & Shale	3164'	R.T.D.	4580'
Shale & Lime	3320'		

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)

Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum


Subscribed and sworn to before me on September 2, 1992.

My commission expires: February 6, 1996.

RECEIVED
STATE CORPORATION COMMISSION

SEP 4 1992

CONSERVATION DIVISION
Wichita, Kansas


Glenda R. Tiffin, Notary Public

