

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 36 TWP. 22S RGE. 22W E/W
Location as in quarters or footage from lines:
C NE NE

Lease Owner C & G Drilling Co
Lease Name Webster #1 Well No. _____
Office Address Box 158, Garfield, Ks. 67529
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 2/25/81
Plugging completed 3/5/81
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.
Producing formation _____ Depth to top _____ bottom _____ T.D. 4601'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	341'	None
				4-1/2"	4600'	2754'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Moved onto location. Plugged off bottom. Pumped 1 sack hulls and 35 sacks cement.
Shot and worked pipe at 3627, 3423, 3220, 3017, 2893 and 2765. Worked pipe free
and pulled a total of 72 joints. Plugged well using 1 sack hulls, 17 sacks gel and
95 sacks cement. Plugging complete.

MAR 17 1981

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING 3-17-81
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 81

My Commission expires: _____



Joan Kelso
Notary Public.

KANSAS


WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 36 T. 22S. R. 22 W

Loc. NE NE

County HODGEMAN

API No. 15 — 083 — 20751-0000
County Number



Elev.: Gr. _____
DF _____ KB 2337'

Operator
C-G Drilling Co., Inc.

Address
1107 Douglas Bldg. Wichita, KS 67202

Well No. 1 Lease Name Webster

Footage Location
660 feet from (N) ~~XX~~ line 660 feet from (E) (W) line

Principal Contractor C-G Drilling Co., Inc. Geologist Vern Schrog

Spud Date 9/3/80 Date Completed 9/12/80 Total Depth 4609 KB P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	337'	Common	185	2% Gel 3% CC
Production		4 1/2"	10 1/2#	4601'	poz salt sat	150	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1981
CONSERVATION DIVISION
Wichita, Kansas

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **C-G Drilling Co., Inc.** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: **Oil**

Well No. **1** Lease Name **Webster**

S 36 T 22R 22W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Heebner	3937	-1600		
Toronto	3972	-1635		
Lansing	3997	-1660		
Stark	4253	-1916		
Marmaton	4372	-2035		
Pawnee	4437	-2100		
Ft Scott	4521	-2184		
Cherokee	4548	-2211		
<p>DST #1: 4358-4415' 15-45-45-45 REC. 30' MUD, 180' FROGGY OIL, IBHP 1292#, FBHP 1003#, IFP 100# FFP 160#</p> <p>DST #2: Miss run</p> <p>DST #3: 4568-4601' 15-45-45-45 REC 245' OCM, IBHP 1417#, FBHP 1407#, IFP 53#, FFP 161#</p>				

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1981

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Data Received

Debra L Heersche
 Signature
 Debra L Heersche, Office Mgr
 Title
 9/17/80
 Date

CONSERVATION DIVISION
Wichita, Kansas