


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

SW SW NW

NORTH



Locate well correctly on above  
Section Flat

Pownee County. Sec. 32 Twp. 22 Rge. 17 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines C - W 1/2 - SW 1/4 NW  
Lease Owner Earl F. Wakefield  
Lease Name Welch Well No. 10  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed May 16 19 55  
Application for plugging filed December 9 19 63  
Application for plugging approved December 10 19 63  
Plugging commenced Dec. 13 19 63  
Plugging completed Dec. 28 19 63  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4280 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	281'	None
				5 1/2"	4276'	3186.80'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4280 feet to surface feet for each plug set.

Sanded up to 4190' dump 5 sacks of cement on bottom. Shot pipe off at 3186'. Pulled pipe from hole, Squeezed well with 20 sacks of mud and 125 sacks of cement.

Well completed.

1-8-64

RECEIVED  
STATE CORPORATION COMMISSION

JAN 8 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.  
Address P.O. Box 313 Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Earl F. Wakefield

Earl F. Wakefield (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield

515 Union Center Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of January, 19 64

My commission expires January 25, 1965

Wanda W. Riley  
Wanda W. Riley

Notary Public.

Welch #1

Owners: Earl F. Wakefield  
& C. I. Ross

Contractor: Earl F. Wakefield  
Comm: 5/3/55 Comp. 5/16/55

SW SW NW  
32 22 17W  
Pawnee County, Kansas  
Casing: 281' of 10 3/4"  
4276' of 5 1/2"

Elevation: 2093 K.B.

Surface	282
Red Bed & Shale	1451
Shale	2125
Lime (Ft. Riley)	2280
Lime & Sand	2395
Lime	2450
Shale & Sand & Shells	2492
Sandy Shale	2603
Shale & Shell	2750
Sand & Shale	2950
Shale	3150
Shale & Shells	3276
Shale	3406
Lime	3595
Lime & Shale	3751
Lime (Lansing)	3761
Lime (Kansas City)	4000
Lime & Shale	4020
Lime	4045
Lime & Shale	4081
Lime	4180
Mss. Chat	4215
Lime	4222
Sand	4240
Shale	4265
Viola Lime	4280
Total Rotary Depth	4280

**RECEIVED**  
STATE CORPORATION COMMISSION

DEC 10 1963

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

I hereby agree and certify that the above is a true and correct copy of the log on the Welch #1 well located SW SW NW, 32-22-17W, Pawnee County, Kansas.

Earl F. Wakefield  
Earl F. Wakefield

Sworn and subscribed before me this 20<sup>th</sup> day of May, 1955.

Ed Davis  
Notary Public

My commission expires July 26, 1958.

