


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pownee County. Sec. 32 Twp. 22 Rge. 17 (E) W (W)  
Location as "NE/CNW&SW" or footage from lines CW<sup>1</sup>/<sub>2</sub> - W<sup>1</sup>/<sub>2</sub> - NW<sup>1</sup>/<sub>4</sub>  
Lease Owner Earl F. Wakefield  
Lease Name Welch Well No. 2  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced Nov. 1 19 63  
Plugging completed Nov. 5 19 63  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4235 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4235 feet to surface feet for each plug set.  
Sanded up to 4200' dump 5 sacks of cement on bottom. Pulled pipe to 600' circ. with mud, Pulled up to 350' pump 20 sacks of cement to 350' pulled pipe out and put 10 sacks on top. Well completed.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 14 1963  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.  
Address P.O. Box 313 Russell, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.  
Earl F. Wakefield (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 12<sup>th</sup> day of November, 1963

My commission expires January 25, 1965  
Wanda H. Riley Notary Public.

WELCH #2  
 OWNERS: EARL F. WAKEFIELD & C.T. ROSS  
 CONTRACTOR: EARL F. WAKEFIELD  
 COMM: 7/7/55 COMP: 7/21/55

SW/2 W/2 NW/4  
 32-22-17W  
 PAWNEE CO., KANS.  
 CASING: 195' of 8 5/8"  
 4228' of 5 1/2"

ELEVATION: 2103 K.B.

Surface	208
Shale & Red Bed	1090
Shale & Shells	1720
Shale	2120
Lime (Ft. Riley)	2480
Lime & Shale	2550
Lime	2715
Shale	3225
" & shells	3365
Lime & Shale	3450
Shale	3525
Lime, Shale & Chert	3598
Sand & Shale	3715
Shale	3760
Lime	4200
Chert	4215
Lime & Shale Brks.	4235
Total Rotary Depth	4235

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 OCT 23 1963  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

I hereby agree and certify that the above is a true and correct copy of the log on the Welch #2 Well located SW/2 W/2 NW/4, 32-22-17W, Pawnee County, Kansas.

Earl F. Wakefield  
 Earl F. Wakefield

Sworn and subscribed before me this 20 day of July, 1955

R. G. Gamble  
 Notary Public

My commission expires Aug 5, 1958  
 July 26, 1958.