

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-20694-00-00
Spot: CNENW Sec/Twnshp/Rge: 34-22S-22W
660 feet from N Section Line, 3300 feet from E Section Line
Lease/Unit Name: CURE INC Well Number: 1-34
County: HODGEMAN Total Vertical Depth: 4489 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1310 WITH 500 SX CMT
Production: Size 4.5 feet: 4488 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/15/2001 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RICHARD LACEY Company: KCC Phone: (620) 225-8888

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING WITH 100# HULLS - 25 SX CMT. DISPLACE TO 4300'. PERFORATE 4 1/2" @ 1200'.
PUMP DOWN 4 1/2" CIRCULATING CMT TO SURFACE WITH 350 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 05/15/2001 1:20 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 4432-4437'. SFL @ 1500'. PUMPED DOWN 4 1/2" CASING WITH 100# HULLS & 50 SX CMT WITH 100# HULLS MIXED IN. DISPLACED WITH 40 BBL OF WATER. MAXIMUM PRESSURE 1800 PSIG. SHUT IN PRESSURE 1500 PSIG. PERFORATED 4 1/2" @ 1325'. PUMPED 295 SX CMT DOWN 4 1/2" CASING CIRCULATING CMT TO SURFACE UP 8 5/8" X 4 1/2" ANNULUS. SHUT IN ANNULUS PRESSURED CMT TO 300 PSIG. SHUT IN AT 200 PSIG.

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 21 2001
5-21-01
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GLE BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

MAY 18 2001

Form CP-2/3