

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-21931-00-00
Spot: E2NENENE Sec/Twnshp/Rge: 28-23S-13E
330 feet from N Section Line, 300 feet from E Section Line
Lease Name: DEHLINGER A Well #: 12
County: GREENWOOD Total Vertical Depth: 2113 feet

Operator License No.: 33640
Op Name: HAAS PETROLEUM, LLC
Address: 10551 BARKLEY ST. #307
OVERLAND PARK, KS 66212

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2106		150 SX
SURF	8.625	40		20 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2016 10:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: MARK HAAS Company: _____ Phone: (913) 499-8373

Proposed Pumping Method: Pump full of cement from top to bottom

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/18/2016 2:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1700', pumped 20 sxs cement, pulled tubing to 700' pumped 20 sxs cement, pulled tubing to 200' pumped 80 sxs cement to surface, gel spacers between cement plugs, casing shot @ 700' & 200'.

Perfs:

RECEIVED
KCC DIST # 3
NOV 21 2016
CHANUTE, KS

mt

Remarks:

Plugged through: TBG

District: 03

Signed Miko Daff
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

NOV 28 2016

CONSERVATION DIVISION
WICHITA, KS

11-28-16

DEC 21 2016

Form CP-2/3



250 N. Water, Ste 200 - Wichita, Ks 67202

HURRICANE SERVICES INC

104 Prairie Plaza Parkway - Garnett, Ks 66032

Customer:	HAAS PETROLEUM, LLC		Customer Name:		Ticket No.:	50956		
Address:			AFE No.:		Date:	11/18/2016		
City, State, Zip:			Job type:	OLD HOLE PLUG				
Service District:	GARNETT, KANSAS		Well Details:	28-23-13				
Well name & No.:	DEHLINGER A 12		Well Location:	GRIDLEY	County:	GREENWOOD	State:	KANSAS
Equipment #	Driver	Equipment #	Driver	Equipment #	Driver	AM	TIME	
25	JAKE					PM	9:30	
203	BEN					AM		
201	KEVIN					PM		
108	RICK					AM	12:30	
						PM		
TRUCK CALLED								
ARRIVED AT JOB								
START OPERATION								
FINISH OPERATION								
RELEASED								
MILES FROM STATION TO WELL							16	

Treatment Summary

ON LOCATION. SAFETY MEETING. SPOT IN AND RIG UP TO TUBING. TUBING AT 1700' MIX AND PUMP GEL 400#. PUMP WATER SPACER. MIX AND PUMP CEMENT 20 SACKS. DISPLACE 5.72 BBL. PULL TUBING TO 700'. MIX AND PUMP 20 SACKS OF CEMENT. DISPLACE 1.85 BBL. PULL TUBING TO 200' MIX AND PUMP CEMENT. 80 SACKS TO SURFACE.

Product/Service Code	Description	Unit of Measure	Quantity	List Price/Unit	Gross Amount	Net Amount
C20101	Cement Pump	ea	1.00	\$790.00	\$790.00	\$653.00
C00101	Heavy Equip. One Way	mi	15.00	\$3.25	\$48.75	\$36.56
C20201	Cement Bulk Truck - Minimum	ea	1.00	\$300.00	\$300.00	\$210.00
P01603	60/40 Pozmix Cement	sack	100.00	\$12.00	\$1,200.00	\$840.00
P01607	Bentonite Gel	lb	344.00	\$0.30	\$103.20	\$72.24
P01607	Bentonite Gel	lb	400.00	\$0.30	\$120.00	\$84.00
C10800	Vacuum Truck 80 bbl	hr	3.00	\$84.00	\$252.00	\$176.40

Received
 KANSAS CORPORATION COMMISSION

NOV 28 2016
 CONSERVATION DIVISION
 WICHITA, KS

TERMS: Cash in advance unless Hurricane Services Inc has approved credit prior to sale. Credit terms of sale for approved accounts are total invoice due on or before the 30th day from the date of invoice. Past due accounts may pay interest on the balance past due at the rate of 1 1/2% per month or the maximum allowable by applicable state or federal laws if such laws limit interest to a lesser amount. In the event it is necessary to employ an agency and/or attorney to affect the collection of said account, Customer hereby agrees to pay all fees directly or indirectly incurred for such collection. In the event that Customer's account with HSI becomes delinquent, HSI has the right to revoke any and all discounts previously applied in arriving at net invoice price. Upon revocation, the full invoice price without discount will become immediately due and owing and subject to collection. Authorization below acknowledges receipt and acceptance of all terms and conditions including the Standard Terms of Sale.

X _____
 CUSTOMER AUTHORIZED AGENT

Customer Comments or Concerns:

Gross: \$ 2,813.95		Net: \$ 1,972.20
Total Taxable	\$ -	Tax Rate: 7.150%
Frec and Acid service treatments designed with intent to increase production on newly drilled or existing wells are not taxable.		Sale Tax: \$ -
		Total: \$ 1,972.20

Date of Service:	11/18/2016
HSI Representative:	JAKE HEARD
Customer Representative:	RANDY BISHOP

DEC 21 2016