

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-22001-00-01
Spot: SWNE Sec/Twp/ship/Rge: 31-33S-38W
3320 feet from S Section Line, 1966 feet from E Section Line
Lease Name: DOWDY A Well #: 1
County: STEVENS Total Vertical Depth: 6400 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5885		WITH 2 SX CMT
PROD	5.5	6234	0	WITH 245 SX CMT
SURF	8.625	1726		WITH 490 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/23/2016 10:00 AM
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 5890' WITH 2 SX CMT. PERFORATE AT 1780' WITH 50 SX CMT (25 SX CM WITH HULLS IN 2ND). PERFORATE AT 600' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/28/2016 2:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

Perfs:

11/23/16: CIBP @ 5885' WITH 2 SX CMT. PERFORATE AT 1780'. PUMPED 490 SX CMT. CMT DID NOT CIRCULATE. WENT ON VACUUM WHEN PUMPING STOPPED. SHUT DOWN. 11/28/16: TOC @ 710'. PERFORATE AT 600'. PUMPED 1.5 BBL PER MINUTE AT 1000 PSI. NO RETURN ON BACKSIDE. TIED ONTO 5 1/2" ANNULUS & PUMPED 75 SX CMT TO 600 PSI & HOLDING. PUMPED 80 SX CMT DOWN 5 1/2" CASING. HOLE STAYED FULL.

Top	Bot	Thru	Comments
5936	5952		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed B. W.

(TECHNICIAN)

RECEIVED
DEC 06 2016
KCC DODGE CITY

SA

Form CP-2/3

DEC 21 2016