

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-20810-00-01  
Spot: W2SWSE Sec/Twnshp/Rgc: 2-23S-22W  
678 feet from S Section Line, 2262 feet from E Section Line  
Lease Name: QUERBACH Well #: 1  
County: HODGEMAN Total Vertical Depth: 4480 feet

Operator License No.: 30104  
Op Name: CAMBRON, PAUL L.  
Address: 118 N PENN PO BOX 384  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4192		
CIBP		4400		
PROD	4.5	4517	0	WITH 150 SX CMT
SURF	8.625	373		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/01/2016 10:30 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-2282

Proposed Plugging Method: RUN CBL & DETERMINE PLUGGING PROCEDURE, CIBP @ 4192' WITH 2 SX CMT. PLUG AT 1400' WITH 50 SX CMT & HULLS THROUGH PERFS. PLUG AT 600' WITH 20 SX CMT. 400' CIRCULATE CMT TO SURFAVCE THROUGH PERFS.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/02/2016 2:10 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

12/1/16: CIBP @ 4400'. TRIED TO LOAD THE HOLE TO RUN THE BOND LOG BUT THE HOLE WOULDN'T LOAD. SET CIBP @ 4192'. SLOWLY LOADED THE HOLE WITH 50 BBL FRESH WATER. RAN CBL. 12/2/16: 1ST PLUG PERFORATE AT 1400' WITH 50 SX CMT WITH 100# HULLS IN THE LAST 25 SX CMT. 2ND PLUG AT 600' WITH 20 SX CMT. 3RD PLUG PERFORATE AT 400' & PUMP 75 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
4455	4460		
4242	4246		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

Signed [Signature]  
5A (TECHNICIAN)

RECEIVED  
DEC 08 2016  
KCC DODGE CITY [Signature]

1766  
Form CP-2/3  
DEC 21 2016