

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-03288-00-00  
Spot: SEWNNE Sec/Twnshp/Rge: 15-10S-25W  
4290 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: ELRICK UNIT Well #: 3-3  
County: GRAHAM Total Vertical Depth: 4025 feet

Operator License No.: 3553  
Op Name: CITATION OIL & GAS CORP.  
Address: 14077 CUTTEN RD PO BOX 690688  
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4024		180 SX
SURF	8.625	210		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2016 9:00 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: LIANA RAMEREZ Company: CITATION OIL AND GAS CORP. Phone: (281) 891-1590

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/400 # hulls!  
8 5/8" surface casing set at 210'.  
5 1/2" production casing set at 4024' w/180 sx cement.  
TD 4025'. PBD 3785' w/ CIBP. DV tool set at 2130' w/500 sx cement.  
Perforations: (below CIBP set @ 3785'). 3982-88, 3960-66, 3938-44, 3907-09, 3897-3901, 3846-52, 3810-15 & 3800-05.  
(Open Perforations): 3764-74, 3751-54, 3370-75, 3166-70, 3096-3100, 3029-34, 3009-14, 2912-16 & 2728-32.  
Junk in hole @ 2356'. 2 7/8 tubing, rods and pump could not be retrieved.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/17/2016 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 2356' and pumped 175 sx cement without hulls, followed by 100 sx cement with 350 # hulls. Cement circulated to surface.  
Pulled tubing to surface.  
Connected to 5 1/2 production casing and pumped 75 sx cement. Cement to surface from 8 5/8 casing. Both casings full of cement.  
GPS -100.09515W & 39.18720N.

Perfs:

Remarks: H & D OILFIELD SERVICES RIG AND ALLIED OFS LLC CEMENT TICKET # 68.216

Plugged through: TBG

District: 04

Signed Darrel Dipman  
KCC WICHITA (TECHNICIAN)

NOV 29 2016  
RECEIVED

11-29-16

DEC 21 2016 <sup>CM</sup> CP-2/3

NOV 21 2016