

KANSAS

Form CP-3  
Rev. 6-4-68STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTRECEIVED  
STATE CORPORATION COMMISSIONJ. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

JUL 21 1975

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Wayne L. Kirkman

Complete Address Box 18148, Wichita, Kansas

Lease Name Bayer Well No. 1

Location C SE Sec. 16 Twp. 22 Rge. (E) (W) 17

County Pawnee Total Depth 3195'

Abandoned Oil Well        Gas Well XX Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Dunbar Casing Pulling, Inc.

Address Great Bend, Kansas License No. 709

Operation Completed: Hour 5:15 P Day 15 Month 7 Year 1975

The above well was plugged as follows:

Total Depth 3195' 8 5/8 csg set 294' cwc.

5 1/2 csg set 2168' cw 125 sk cem. Top perf. (2168')

Filled 5 1/2 csg with sand (2168-1950') dumped 4 sk cem. W/dump bailer. (1950-1920)

Cutoff & recovered 1630' of 5 1/2 csg.

Set 100 sk cem. plug (750'-500') thru 5 1/2 csg.

Gel & water (500'-275') thru 5 1/2 csg. (22 Sk)

100 sk cem. plug from 275' to base of cellar thru 5 1/2 csg.

I hereby certify that the above well was plugged as herein stated.

Signed: B. L. H. Massey  
Well Plugging Supervisor

INVOICED

DATE

7/23/75

INV. NO.

1653-W