

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Alpine Drilling Co., Inc.
Complete Address 800 Bitting Bldg., Wichita, Kansas 67202
Lease Name Lewis "A" Well No. 1
Location C E/2 SE Sec. 10 Twp. 22 Rge. (E) (W) 17
County Pawnee Total Depth 4075'
Abandoned Oil Well XX Gas Well XX Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Glenn & Smith Pipe Pulling
Address Box 156 Ellinwood, Kansas 67526 License No. 396
Operation Completed: Hour 4:45 P Day 19 Month 12 Year 1972

The above well was plugged as follows:

Total Depth 4075' 8 5/8 csg set at 1054' cwc 400 sk.

5 1/2 csg set at 4073' cw 100 sk cmt. FBTD 4004' and perf. at 3897'.

Filled 5 1/2 csg W/sd (~~3880-4004~~) Dumped 5 sk cmt W/dump bailer. (~~3845-3860~~)

Cutoff and recovered 3157' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 315'--Set rock & sand bridge (315-309)

Dumped 5 yds readymix cmt from 300' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/22/72

INV. NO. 6957-W

Signed: Leo F. Massey
Well Plugging Supervisor