

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Alpine Drilling Co., Inc.
Complete Address 500 Bitting Bldg., Wichita, Kansas 67202
Lease Name Johnson Well No. 1
Location SE SW Sec. 11 Twp. 22 Rge. (E) (W) 17
County Pawnee Total Depth 4122'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Pipe Pulling
Address Box 176 Chase, Kansas 67524 License No. 683
Operation Completed: Hour 10:45 A Day 3 Month 12 Year 1973

The above well was plugged as follows:

Total Depth 4122' 18" csg 41' cwa 8 5/8 csg set at 960' cwa

4 1/2 csg set at 4118' cw 100 sk cem.

4 1/2 csg PBT 4056' with top perf. (3962')

Filled 4 1/2 csg W/sd: (3940'-4056') dumped 3 sk cem. W/dump bailer/ (3905-3940)

Cutoff and recovered 3117' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug

and pumped 100 sk comm cement by Allied Cementing Co. Max PP 300 lbs. SIP 150#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/10/73

INV. NO. 8267-W

Signed: Leo F. Mandy
Well Plugging Supervisor