

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1976
11-29-76

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 145-20338-0000 (of this well)

Operator's Full Name Hummon Oil Company

Complete Address 860 Sutton Place, Wichita, Kansas 67202

Lease Name Rubby Compton Well No. 1

Location C NW NE SE Sec. 3 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 3949'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11 A Day 24 Month 11 Year 1976

The above well was plugged as follows:

Total Depth 3949' 8 5/8 csg set 292' cwc 225 sx.

5 1/2 csg set 3934' cw 125 sx cem.

5 1/2 csg PBSD 3934' with top perf. (3689-93)

Set 5 1/2 wood plug at 3600' -poured 10' sand -dumped 4 sk cem W/dump bailer. (3600-3560)

Allied Cementing Co. mixed & pumped down anulus with 20 sk gel & 60 sx Baroid. with water.

Cutoff & recovered 3022' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 125 sx "Comm Cem. & shutin.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 11-30-76

INV. NO. 4237-W