

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Barnett Oil Company

Complete Address 411 First National Bank Bldg., Wichita, Kansas 67202

Lease Name Armstrong Well No. 1

Location NW NW SW Sec. 7 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 4130'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Santa Fe Pipe & Supply

Address Box 562 Great Bend, Kansas 67530 License No. 574

Operation Completed: Hour 10:30 A Day 1 Month 3 Year 1972

The above well was plugged as follows:

Total Depth: 4130' 20 3/4 csg set at 648' cwc:

4 1/2 csg set at 4129.5 cw 175 sk cmt.

4 1/2 csg PBSD 3969' with perf. (3930-3932)

Filled 4 1/2 csg W/sd' (3900-3969) Dumped 4 sk cmt W/dump bailer. (3865-3900)

Cutoff and recovered 2781' of 4 1/2 csg.

Pumped down 10 3/4 csg with 30 sk gel & water W/300 lbs hulls, -released 10 3/4 plug
and pumped 160 sk 50-50 poz cmt 2 1/2 gel. SI pres. 500 lbs. By HONCO

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Muesel
Well Plugging Supervisor

DATE 3-6-72

INV. NO. 5295-10