

State of Kansas



FORM - CP-2

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 23 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Townsend of Livingston Oil Co. has this

date requested permission to plug the following described well:

Mr. Townsend guarantees payment of the plugging fee.

Operator's full Name: Livingston Oil Co.

Complete Address: Box 1797 Tulsa, Okla.

Lease Name: Cook Well No. 25-41

Location: C NW /4 Sec. 25 Twp. 24S Rge. 41 (E) (W)

County Hamilton Total Depth 2380 Oil Well

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Townsend was instructed to plug the well as follows:

7 5/8"-312' Circulated w/cement. 4 1/2"-2379' Circulated w/cement.

Top perforations 2362' Plug bottom w/20 Sax.cement top cement 2150'

Mud 2150' to 350' Spotted 10 Sax.cement 350' to 250'

Mud 250' to 50' Plug, 5 Sax.cement 50' to 0

Very truly yours,

*Hugh Scott*  
Conservation Division Agent