

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 21 1963
 1-21-63
 CONSERVATION DIVISION
 Wichita, Kansas

Jan. 9, 1963.

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Walter Voth of Knight Caseing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Walter Voth guarantees payment of the plugging fee.

Operator's full Name: Allan, Thos. H.

Complete Address: 925 Union Center Wichita, Kansas.

Lease Name: McKee #1 Well No. #1

Location: G/2-NE-SW Sec. 9 Twp. 22 Rge. 8 (E) (W) Abandoned

County Reno, County Total Depth 3475' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Walter Voth was instructed to plug the well as follows:

3466' of 5 1/2" long string. Sanded to 3450' & 5 sacks cement.

195' of 8 5/8" surface pipe circulated with cement. Hole

filled to 180' with mud, 10' rock bridge & 20 sacks cement.

Hole filled to 40' with mud, 10' rock bridge & 10 sacks

cement to base of cellar. 2850' of 5 1/2" pipe pulled.

Very truly yours,

Hummer Justus
 Conservation Division Agent