

15-095-20056-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

DEC 21 1967
2-21-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed December 5, 1967.

Dear Sir:

Mr. Wayne Dobbs of Edmiston Drilling Co. has this
date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Ks. 67202

Lease Name: Schafler ^{Schafler} _{see} Well No. # 1

Location: C SE SE Sec. 23 Twp. 30 Rge. 10 (E)(W) W

County Kingman Total Depth 4791' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

235' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill hole with drilling mud to 225', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks of cement, bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving
Conservation Division Agent