



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Branan of Bunkerhill Oil Producers has this date requested permission to plug the following described well:

Mr. R. L. Branan guarantees payment of the plugging fee.

Operator's full Name: Bunkerhill Oil Producers

Complete Address: P. O. Box 371, Claflin, Kansas 67525

Lease Name: H. H. Pierce Well No. # 2

Location: NE NW SE Sec. 2 Twp. 14 Rge. 15 (E)(W) W

County: Russell Total Depth 3311 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

15 1/2" csg. 285'.

Sanded hole back to 3200' & dumped 5 sax cement with dump bailer.

Pulled pipe to 600', circulated hole with mud & displaced 50 sax

cement @ 500'. Pulled pipe to 300' & displaced 50 sax cement. Pulled

remaining pipe. Mud to 30' & displaced 25 sax cement with pump truck,

cementing to base of cellar.

Very truly yours,

Don Lewis
Conservation Division Agent