



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 7 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Louis M. Mai of Louis M. Mai has this
date requested permission to plug the following described well:

Mr. Louis M. Mai guarantees payment of the plugging fee.

Operator's full Name: Louis M. Mai

Complete Address: Box 33, Russell, Kansas 67665

Lease Name: Crawford Well No. # 10

Location: NE NW SW Sec. 2 Twp. 14 Rge. 15 (E)(W) W

County: Russell Total Depth 3308 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Don Wolfe was instructed to plug the well as follows:

12 1/2" csg. 905'. 7" csg. 3303'. Perf. 3072'.

Sanded hole back to 3000' & dumped 6 sax cement with dump bailer. Pulled
pipe to 880', circulated hole with 5 sax hulls, 30 sax mud, plug, 2 sax hulls,
& displaced 75 sax cement thru 7" csg. Pulled remaining pipe, set 20' rock
bridge @ 320' & displaced 75 sax cement. Mud to 60', set 10' rock bridge, &
displaced 50 sax cement with Halliburton Cementing Company's pump truck,
cementing to base of cellar.

Don Wolfe
Conservation Division Agent